No.	Items of work	Per Unit	Quantity	Rate in Words	Rate in Figures
				Rs. a. p.	Rs. a. p.
26	Fencing alround 4 rows of barbed wire and L iron posts 2″×2″×3-16″ at every 10 ft. apart and corner streets, etc., complete	R.ft.	210		
	Abstract estimate for sinking a well 4′×4′ inner dimension).				
1	Earthwork excavation in gravelly soil	C.yd.	14¼		
2	Excavation in soft rock 6′ to 12′	,,	14¼		
3	Blasting hard rock with gun powder—				
	12′ to 15′	,,	1·8		
	15′ to 18′	,,	1·8		
	18′ to 21′	,,	1·8		
	21′ to 24′	,,	1·8		
	24′ to 27′	,,	1·8		
	27′ to 30′	,,	1·8		
4	Blasting hard rock with dynamite—				
	30′ to 36′	,,	3·6		
	36′ to 42′	,,	3·6		
	42′ to 45′	,,	3·6		
5	Burnt stone slabs 6″ thick dressed and fixed at bottom and top of stone steining	S.ft.	153		
6	Two line dressing slabs	,,	87		
7	Cutting grooves in slabs	Each	2		
8	Size stone in lime mortar	C.ft.	594		
9	Cement pointing 1 : 3	Sqr.	3·02		
10	Providing and fixing R. S. joists including drilling holes, clamps, etc., complete	Cwt.	0·9		
11	Providing an iron pulley with all fittings, etc., complete	Each	1		
12	Unforeseen works such as levelling and trimming the sides, etc., complete	S.yd.			

S. RAMASWAMY,
Executive Engineer.

MEDICAL DEPARTMENT.

OFFICE OF THE DISTRICT MEDICAL OFFICER, TUMKUR DISTRICT.

Notice dated 16th April 1940.

The public are hereby informed that the date of sale by auction of certain obsolete books of the District Hospital, Tumkur, which was fixed for 22nd April 1940 as per *Gazette Notification*, dated 3rd April 1940, is postponed until further orders from the Senior Surgeon's Office.

S. V. BILIGIRI IYENGAR,
District Medical Officer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF PUBLIC INSTRUCTION.

GOVERNMENT HIGH SCHOOL, MALLESWARAM, BANGALORE.

Notification No. 2083 *of* 1939-40.

It is hereby notified that an old bicycle will be sold by auction on Monday the 20th May 1940 at 4-45 P.M. in the school premises.